

# Measurement Controls, Inc.

## Test meters



- Meters repaired with quality/warranty
- Since 60's
- Parts/meter connections
- Flow rates: From ½ LPM (1.1cuft)
- Accuracy: +/-0.5% (Also proved under various EPA methods)
- Calibration: Standard Bells traceable to N.I.S.T.
- W. Pressure: 0.1 - 0.5 in WC
- Connection: Either top or side
- Meter Size: From 110 to 425 Cfh
- Output: Index reading, Data lodger, Or LCD
- Meter Management System
- Re-manufactured/repared
- Timely delivery

[Sales@measurementcontrols.com](mailto:Sales@measurementcontrols.com)

P. O. Box 562775

Charlotte, NC 28256-2775

Tel: (800) 714-9486

Fax: (704) 921-1010